(10) The contractor is responsible for all accidents to workmen, etc., on the work, and he must take precaution against all risk of accidents and, if necessary, provide for the same by insurance at the proper time.

Note.—(*b*) It is the business of the contractor to make his own arrangements for quarries and supplies of materials.

Abstract Estimate for increasing the capacity of Amchihally Amchikatte Minor Tank, Krishnarajpet Taluk.

No.	Items of work	Unit	Quantity	Rate
	I. Bund.			Rs. a. p.
1	Earthwork embankment with watering and consolidation	C.yd.	11,014	0 4 0
2	Turfing to bund	Sqr.	535	0 9 0
3	Constructing rough stone revetment in front of bund, including gravel backing to revetment	C.yd.	344	1 12 0
4	Removing date trees and jungle	Grade	12	2 0 0
5	Cutting grips in bund	,,	12	2 0 0
6	Removing and refixing grade stones	No.	8	0 4 0
7	Supplying and fixing new grade stones	,,	7	1 12 0
	II. Constructing a new C. I. pipe sluice 8" dia.			
1	Earthwork excavating foundation	C.yd.	70	0 4 0
2	Concrete in surki mortar	C.ft.	155	0 4 0
3	Size stone in surki mortar	,,	81	0 4 0
4	Deep cement pointing 1 : 3	Sqr.	0.80	4 0 0
5	Supplying and fixing burnt stone slabs 6" thick on top of front head wall	S.ft.	9	0 8 0
6	Supplying and fixing 8" C. I. pipe for sluice	R.ft.	36	4 0 0
7	Constructing rough stone revetment for wings in rear	C.yd.	9	1 12 0
8	Refilling bund with watering and consolidation (bund excavation)	C.yd.	63	0 2 0
9	Unforeseen charges such as jally wood plug and rod, etc.	..	L. S.	..
	III. Raising the waste weir from R. L. 50.00 to 54.00.			
1	Earthwork excavation for foundation in hard gravel and soft rock	C.yd.	3	0 4 0
2	Dismantling the old masonry body wall	C.ft.	220	0 0 3
3	Concrete with stone jelly in surki mortar	,,	39	0 4 0
4	Size stone in surki mortar	C.ft.	1,260½	0 4 0
5	Deep cement pointing 1 : 3	Sqr.	14.01	4 0 0
6	Constructing rough stone revetment (new)	C.yd.	10	1 12 0
7	Earthwork ramping in front of body wall of weir inside including watering and consolidation, etc., complete	C.yd.	554	0 4 0
8	Earthwork to flank bund including watering and consolidation, etc., complete	,,	42	0 4 0
9	Filling the heart of Apron below the pitching with boulders and jelly, etc., complete	,,	102	0 8 0
10	Removing and resetting old rough stone revetment with new jelly wedging, etc., complete	,,	122	0 12 0
11	Unforeseen charges and miscellaneous works, etc.	..	L. S.	..

B. S. NARASINGA RAO,
Executive Engineer.

SHIMOGA DIVISION.

Abstract Notification dated the 12th July 1940.

The attention of the public is drawn to the notification calling for tenders for improvements to the Ghat section of Agumbe Ghat at miles 57, 58 and 59 published in pages 1684-1687, Part VI of the *Mysore Gazette*, dated 18th July 1940.

Tenders will be received by the Executive Engineer, Shimoga Division, up to 3 P.M. on 5th of August 1940.

Earnest money required for the work is Rs. 1,500 which should be credited to the Treasury to "17 (*a*) P. W. Deposits" and challan enclosed.

Notification dated 17th July 1940.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Shimoga Division, up to 3 P.M. on 10th August 1940, for restoring Bandigadi Hosakere (Minor Tank) Reg. No. 920, Tirthahalli Taluk. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of December 1940.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Shimoga between the hours of 11 A.M. and 5 P.M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer on payment of annas four (0-4-0) per form. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a Treasury challan of Rs. 90, credited to "17 (a) P.W. Deposits" in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for Restoring Bandigadi Hosakere (Minor Tank) Reg. No. 920, Tirthahalli Taluk, in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Executive Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond, in default of which his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the Notice Board in the Executive Engineer's Office in due course. No enquiry regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

9. Rates once tendered will not be enhanced on any account.

10. Rates for non-tendered and non-estimated items shall be as per schedule rates of the Department or those fixed by the Executive Engineer after working out data with not more than 10 per cent for contractor's profit.

11. In all matters not specifically provided for and in all matters of dispute about rates, quantities, measurements, quality of works, etc., and in all disputes of any kind, the decision of the Executive Engineer will be final and legally binding.

12. Quotations must be given in words as well as in figures and they must be in specific term of unit shown against each item of work. Any quotation quoted at so much percentage less or more than estimated rate will not be accepted.

13. Chamundy brand cement should be used for the works.

14. A reserve of 5 per cent on the value of work done will be withheld from the bills towards security deposit.

Abstract estimate for restoring Bandigadi Hosakere (Minor) Reg. No. 920 of Muttur Hobli, Tirthahally Taluk.

Item No.	Description of work	Unit	Rate	Quantity
	Bund R. L. 55·00 Top width 4½′ slope 2 : 1.		Rs. a. p.	
1	Cutting grips and trenches to the bund to retain new earth	Grade	3 0 0	7
2	Earthwork to bund with watering and consolidation, etc., complete	C.yd.	0 6 0	1,526
3	Turfing the slopes of bund	Sqr.	0 10 0	229
4	(*a*) Providing grade stones with figuring and painting, etc.	Each	2 8 0	7
	(*b*) Providing Index stones	,,	1 0 0	7
	(*c*) Providing and fixing B. M. stones	,,	4 8 0	2
	(*d*) Providing one Reg. No. and date stone with figuring and painting, etc., complete	,,	10 0 0	1
	(*e*) Providing and fixing two iron gauge plates one near the sluice, and one near waste weir (gauges to be supplied departmentally)	,,	10 0 0	2

Item No.	Description of work	Unit	Rate	Quantity
			Rs. a. p.	
	Constructing a masonry waste weir 50·00.			
1	Earthwork excavation for foundation body wall in loose gravelly soil	C.yd.	0 4 0	18
2	Stone jelly concrete in cement mortar 1 : 4 : 8 for foundation	C.ft.	0 7 0	100
3	Size stone in cement mortar for foundation and superstructure	,,	0 8 0	382
4	B. S. slabs 6″ thick roughly dressed and fixed	S.ft.	0 12 0	36
5	Rough stone work (new)	C.yd.	2 8 0	26
	Miscellaneous Works.			
1	Clearing thick and thin jungle, removing ant-hills, etc., on the bund	..	Lumpsum	..
2	Excavating a check-drain on the upper side of the tank and using the stuff for banking, etc.	C.yd.	0 4 0	267
3	Unforeseen and miscellaneous works	..	Lumpsum	..
	C. I. pipe sluice at R. L. 45·50.			
1	Cutting open the bund and refilling the same with watering and consolidation	C.yd.	0 6 0	83
2	Earthwork excavation for foundation of front head wall and wing	,,	0 4 0	6
3	Baling out water, putting ring bund, etc.	..	Lumpsum	..
4	Stone jelly concrete in cement mortar 1 : 4 : 8	C.ft.	0 7 0	173
5	Total size stone in cement mortar 1 : 6	,,	0 8 0	166
6	(*a*) Cement concrete coping 1 : 2 : 4 6″ over head wall	C.ft.	1 0 0	5
	(*b*) B. S. slab 6″ thick roughly dressed and fixed in cement mortar guide slab	S.ft.	0 12 0	21
7	Providing and fixing 6″ dia. C. I. pipes including cart hire, railway freight, etc., complete	R.ft.	2 8 0	36
8	Drilling holes in slabs	Each	1 0 0	4
9	Fixing the pipes and cogging the joints	,,	2 0 0	3
10	Providing and fixing T. W. plug with iron rod with locking arrangements	,,	10 0 0	1
11	Rough stone revetment (new)	C.yd.	2 8 0	20
12	Cement pointing and plastering to masonry, unforeseen works, etc.	..	Lumpsum	..

Notification dated 17th July 1940.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Shimoga Division, up to 3 P.M. on 10th August 1940, for restoring Heggod-Urubagilakere or Jodukere (Minor Tank) Reg. No. 163 (Sagar Taluk). An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of December 1940.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Shimoga between the hours of 11 A.M. and 5 P.M.

3. Tender should be submitted on printed forms which may be obtained from the Executive Engineer on payment of annas four per form. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a treasury challan for Rs. 90 credited to the Treasury under "17 (*a*) P. W. Deposits," in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for restoring Heggod-Urubagilakere or Jodukere (Minor Tank) Reg. No. 163, Sagar Taluk," in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Executive Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender the successful competitor will be required to execute the usual contract bond, in default of which his tender will be considered cancelled and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the Notice Board in the Executive Engineer's Office in due course. No enquiry regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders the earnest money on rejected tenders will be returned.

9. Rates once tendered will not be enhanced on any account.

10. Rates for non-tendered and non-estimated items shall be as per schedule rates of the Department or those fixed by the Executive Engineer after working out data with not more than 10 per cent for contractor's profit.

11. In all matters not specifically provided for and in all matters of dispute about rates, quantities, measurements, quality of works, etc., and in all disputes of any kind, the decision of the Executive Engineer will be final and legally binding.

12. Quotations must be given in words, as well as in figures and they must be in specific term of unit shown against each item of work. Any quotation quoted at so much percentage less or more than estimated rate will not be accepted.

13. Chamundy brand cement should be used for the work.

14. A reserve of 5 per cent on the value of work done will be withheld from the bills towards the security deposit.

Abstract estimate for restoring Heggod-Urubagilakere or Jodukere, R. No. 163 of Sagar Taluk (Minor).

Item No.	Description of work	Unit	Rate	Quantity
	I. Bund R. L. 54·00.		Rs. a. p.	
1	(*a*) Jungle clearing, cutting and rooting out trees, etc.		Lumpsum	
	(*b*) Cutting grips and steps		,,	
2	Earthwork to bund including watering and consolidation (earth to be got from flanks and approach and draft of weir)	C.yd.	0 7 0	710
3	Turfing the slopes of bund front and rear	Sqr.	0 10 0	99·00
4	Providing and fixing B. M. stones on cement concrete bed including figuring, etc., complete	Each	4 8 0	2
5	Do do Reg. No. stones	,,	10 0 0	1
6	Do do grade stones	,,	2 8 0	3
7	Do do Index stones	,,	1 0 0	3
	II. Constructing a 6″ C. I. pipe sluice at R. L. 41·00 (C. S. 4).			
1	Putting up a ring bund with earth work alround 3 sides if found necessary	C.yd.	0 4 0	170
2	Cutting open the bund and refilling including watering and consolidation	,,	0 5 0	103
3	Excavation for foundation	,,	0 4 0	12
4	Stone jelly concrete in cement mortar 1 : 5 : 10	C.ft.	0 7 0	369
5	Cut laterite in cement mortar 1 : 6 excluding top slabs	,,	0 7 0	606
6	Providing and fixing cement concrete slab (1 : 2 : 4) including plastering	,,	1 0 0	35
7	Providing and fixing B. S. slab 4″ to 6″ thick	S.ft.	1 0 0	22
8	Drilling holes in B. S. slabs	Each	1 0 0	4
9	Providing and fixing 6″ dia. C. I. pipe including cart-hire etc., complete	R.ft.	3 0 0	36
10	Cement mortar plastering 1 : 3	Sqr.	9 8 0	2·50
11	Providing, fixing T. W. plug and rod with locking arrangements	Each	15 0 0	1
12	Cut laterite revetment in front of the front wall including foundation	C.yd.	3 0 0	23
13	Excavation of foundation for revetment	,,	0 4 0	19
	III. Constructing a waste weir at R. L. 50·00.			
1	(*a*) Earthwork clearing the approach of draft channels and using the same for the lower side of waste weir halla	C.yd.	0 5 0	113

Item No.	Description of work	Unit	Rate	Quantity
			Rs. a. p.	
	(*b*) Excavation for foundation of body wall including bank connections in gravelly soil	C.yd.	0 4 0	11
2	Stone jelly concrete in cement mortar (1 : 5 : 10) for body wall	C.ft.	0 7 0	96
3	Cut laterite in cement mortar 1 : 6	,,	0 7 0	95
4	Cement concrete slab 1 : 2 : 4 including plastering ..	,,	1 0 0	35
5	Cement mortar plastering 1 : 3 to exposed portion ..	Sqr.	9 8 0	1·00
6	Cut laterite revetment for sides of bunds at weir ..	C.yd.	3 0 0	27
7	Excavation for foundation of revetments	..	Lumpsum	..

D. A. HUKERI,
Executive Engineer.

MEDICAL DEPARTMENT.

OFFICE OF THE MEDICAL OFFICER, P. K. SANATORIUM, MYSORE.

Abstract Notification dated 12th July 1940.

Notice is hereby given that sealed tenders, in triplicate, on half sheet foolscap size paper for the supply of "Bedding and Clothing" required for Princess Krishnajammanni Sanatorium, Mysore, will be received by the undersigned in his office at 11 A.M. on Monday the 5th August 1940. For full particulars please refer to page 1639, Part VI of the *Mysore Gazette*, dated 11th July 1940.

ABDUL KHALIQ SHERIFF,
Medical Officer.

EPIDEMIC DISEASES HOSPITAL, MYSORE.

Tender Notice dated 1st July 1940.

1. Notice is hereby given that sealed tenders (in triplicate) on half-sheet of foolscap size paper will be received at the Office of the Medical Officer, Epidemic Diseases Hospital, Mysore, by the undersigned at 9-30 A.M., on Monday the 19th August 1940, for the year 1940-41.

2. No tender will be received after the date and hour abovementioned.

3. Tenders should be superscribed " Tender for the supply of bedding and clothing to the Epidemic Diseases Hospital, Mysore."

4. No tender will be received unless accompanied by a deposit of Rs. 50 in Treasury receipt.

5. Tenders will be opened by the Medical Officer, on the date and at the hour abovementioned in the presence of such tenderers, as may choose to attend.

6. The rate of each item must be specified in figures as well as in words and they must be for the particular kind of the articles as specified in the list appended. The value of each teder must be worked out according to the rates tendered and the total value must also be entered in ink. Tenders not conforming to this rule will be rejected.

7. The quantities stated in the list are not guaranteed.

8. The Senior Surgeon does not bind himself to accept the lowest or any other tender, or to assign any reason for not accepting the tender.

9. The deposit of the successful tenderer will be returned after the whole quantity of linen is supplied. The linen should be supplied within 15 days from the date of order.

10. No advance of cash will be made to the contractor. Payment will be made as early as possible on his producing the necessary bill for the whole quantities supplied.

11. In case the contractor fails to comply with the order given to him, he shall forfeit the deposit money to Government and also be bound to make good to Government any loss which may arise from such cessation.